



WBE certified company

# Hot Weather Concrete



**Steven N. Moore, PE, Senior Engineer**  
**Atlantic Testing Laboratories**

The American Concrete Institute (ACI) defines 'Hot Weather' as high ambient temperatures, high concrete temperatures, low relative humidity, high wind speed, solar radiation, or any combination that will impair the quality of concrete due to accelerated moisture loss and/or cement hydration. Most summer days in New York State would qualify as 'Hot Weather', using ACI's definition.

The best approach for mitigation is to control the concrete temperature and protect fresh concrete from rapid moisture loss. Producers often cover aggregate stockpiles as protection from solar radiation. Alternatively, stockpiles may be sprayed with water, typically well water, which averages about 45°F in the Northeast. Controlling the aggregate temperature is a common and economical practice, since lowering the aggregate temperature by 2°F will lower the final mix temperature by approximately 1°F.

Controlling temperatures and moisture loss during and after placement is equally important and can be achieved through planning and preparation. Placing concrete in the early morning is advantageous, especially for flatwork placements with large, exposed surface areas. Moist curing with spray foggers, applying sheet membranes or curing compounds, and/or covering flatwork will protect placements from moisture loss. Vertical placements, such as bridge abutments, should be protected at the top surface to avoid rapid drying and shrinkage. Additional mitigation methods include using chilled mix water, replacing water with ice chips or flakes (equal parts by mass), and nitrogen cooling, which is more popular in southern states.



Ice flakes are often used to control concrete mix temperatures during the summer months.

ACI also recommends avoiding rapid heat loss/gain, which is defined as more than 5°F/hour or 50°F in 24 hours, since this could lead to thermal shock and excessive cracking. Additional information and guidance can be found in ACI 305R-20, "Guide to Hot Weather Concreting" (updated in 2020), and ACI 305.1-14, "Specification for Hot Weather Concreting" (reapproved 2020).

Without proper planning and mitigation, hot weather can cause challenges, including:

- increased slump loss and water demand, which could lead to decreased strength and durability;
- increased rate of setting, which could lead to issues with flatwork finishing and long term durability;
- plastic shrinkage cracking, which can increase the permeability and also affect long term durability, especially on surfaces exposed to de-icing chemicals;
- difficulties controlling entrained air content, which can also affect durability and strength.

$$T = \frac{0.22(T_a W_a + T_c W_c) + T_w W_w + T_a W_{wa}}{0.22(W_a + W_c) + W_w + W_{wa}}$$

ACI 305R-20 formula for predicting the temperature of freshly mixed concrete.

ATL, a WBE certified company, can develop concrete mix designs, perform laboratory trial batches for mix verification, apply the Maturity Method to estimate in-place concrete strength, and monitor internal curing temperatures using embedded thermocouples.

For more information, contact Steven N. Moore, PE, at (315) 386-4578 or [SMoore@AtlanticTesting.com](mailto:SMoore@AtlanticTesting.com).

## **ASSOCIATED SERVICES**

[Construction Materials Engineering and Testing](#)

[Special Inspections](#)

[Concrete Investigative Services](#)

[Petrography Services](#)



This document is for general informational purposes only and is provided with the understanding that the authors are not herein engaged in rendering professional advice or services. Site specific circumstances make each project unique. As a consequence, information in this document may be incomplete, inaccurate, or inapplicable to particular situations or conditions. Any use of this information should take into account all relevant factors and sources of information applicable to a project. We do not accept responsibility for any omission, inaccuracy, or error in this document, or any action taken in reliance thereon.